

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-03932-00-00
Spot: SESWE Sec/Twnshp/Rge: 8-20S-9W
3297 feet from S Section Line, 1851 feet from E Section Line
Lease Name: PROFFITT Well #: 3
County: RICE Total Vertical Depth: 3248 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S MAIN ST
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	289		
PROD	5.5	3222		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/30/2011 7:45 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: JEFF KLOCK Witness Type: NONE
Date/Time Plugging Completed: 11/30/2011 4:15 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, HAD CASING LEAK AT 1100 - 1150'. THIS WELL HAS BEEN SQUEEZED IN PAST -- NO RECORDS. AFTER PULLING TUBING FROM THE WELL, COULD NOT MILL PAST 1180'. PERFORATE AT 1180', 800', AND 320'. RUN TUBING TO 1180', AND PUMP 35 SX'S COMMON CEMENT. LET SET AWHILE AND TAG CEMENT AT 850'. PULL TUBING TO 800', AND PUMP 35 SX'S COMMON CEMENT. LET SET AWHILE AND TAG CEMENT AT 450'. PULL TUBING TO 320' AND ATTEMPT TO CIRCULATE TO SURFACE. COULDN'T CIRCULATE CEMENT. RUN 1" DOWN BACKSIDE OF PROD. CASING AND CIRCUALTE CEMENT TO SURFACE. PULL ALL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3222	3247	CSG	ARBUCKLE

Remarks: EMERGENCY PLUGGING REQUEST GRANTED BY JEFF KLOCK ON 11-30-11. LOG TECH OF KS TICKET 6836. COPELAND C-39458.

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

RECEIVED

Form CP-2/3

DEC 16 2011

12/23/11

KCC WICHITA