

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-00930-00-01  
Spot: N2NWNW Sec/Twnshp/Rge: 16-29S-6W  
4990 feet from S Section Line, 4675 feet from E Section Line  
Lease Name: PINKERTON Well #: SWD 1  
County: KINGMAN Total Vertical Depth: 4174 feet

Operator License No.: 5348  
Op Name: CAMPBELL, ROBERT E.  
Address: 260 N ROCK RD STE 110  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	215		200 SX
PROD	5.5	4173		150 SX

Well Type: SWD UIC Docket No: D16361.0 Date/Time to Plug: 11/18/2011 8:00 AM  
Plug Co. License No.: 30346 Plug Co. Name: SHAWNEE WELL SERVICE, INC.  
Proposal Rcvd. from: JEFF CAPPS Company: SHAWNEE WELL SERVICE Phone: (316) 685-6001

Proposed Plugging Method: UNABLE TO GET TO BOTTOM. WASHED DOWN & FISHED TO 2500' DECIDED TO GIVE UP & PLUG:

Plugging Proposal Received By: STEVE VANGIESON Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/23/2011 2:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Perfs:

RAN WASHOVER PIPE TO 2500', COULD NOT FISH TUBING OUT. SPOTTED 35 SX CMT THRU TUBING AT 2756' TAGGED CMT AT 2644'. TIED ONTO 5 1/2 CASING AND PUMPED 120 SKS DOWN CASING. LET SET 2 HRS AND TAGGED CMT AT 925'. PRESSURE TESTED CASING FROM 925'- 0' HELD 100#. PERFORATED CASING AT 545' & PUMPED 35 SX CMT. TAGGED CMT AT 325'. PERFORATED CASING AT 250' & CIRCULATED CMT TO SURFACE.

Remarks: ALLIED CMT 60/40 4% GEL & CLASS A 3% CACL

Plugged through: TBG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

*[Handwritten Signature]*  
cc to MIC 12/16/11

RECEIVED

DEC 16 2011

Form CP-2/3

12/23/11

KCC WICHITA

✓