

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-21101-00-00
Spot: SWNWNW Sec/Twnshp/Rge: 34-15S-29W
4290 feet from S Section Line, 4950 feet from E Section Line
Lease Name: DOWELL C Well #: 1
County: GOVE Total Vertical Depth: 4365 feet

Operator License No.: 7775
Op Name: WILTON PETROLEUM, INC.
Address: PO BOX 391
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	298	0	165 SX
PROD	5.5	4365	0	200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/30/2011 11:30 AM
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.
Proposal Rcvd. from: BERNIE RUNDSTROM Company: WILTON PETROLEUM, INC. Phone: (620) 628-4466

Proposed Plugging Method: Ordered 390 sxs 60/40 pozmix - 4% gel - 500# hulls - 14 sxs gel spacer.
Top down plug.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/30/2011 1:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 298' w/165 sxs cement.
5 1/2" production casing set at 4365' w/200 sxs cement.
TD 4365'. DV Tool at 1985' w/350 sxs cement.
Connected to 5 1/2" production casing - pumped 50 sxs cement mixed with 200# hulls - followed with 14 sxs gel and 245 sxs cement mixed with 300# hulls.
Max. P.S.I. 800#.
Connected to 8 5/8" surface casing - pumped zero sxs cement.
Max. P.S.I. 500#.

Perfs:

Top	Bot	Thru	Comments
3944	3978		KC

Remarks: SWIFT CEMENTING COMPANY-TICKET #20465.

Plugged through: CSG

District: 04

Signed

Darrel Dipman

(TECHNICIAN)

RECEIVED

DEC 16 2011

✓ 12/23/11

KCC WICHITA CP-2/3

DEC 08 2011