

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-063-21151-00-00  
Spot: NWSWNW Sec/Twnshp/Rge: 34-15S-29W  
3630 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: DOWELL C Well #: 2  
County: GOVE Total Vertical Depth: 4327 feet

Operator License No.: 7775  
Op Name: WILTON PETROLEUM, INC.  
Address: PO BOX 391  
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	238	0	245 SX
PROD	5.5	4324	0	200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/30/2011 9:00 AM  
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.  
Proposal Rcvd. from: BERNIE RUNDSTROM Company: WILTON PETROLEUM, INC. Phone: (620) 628-4466

Proposed Plugging Method: Ordered 380 sxs 60/40 pozmix - 4% gel - 500# hulls- 14 sxs gel spacer.  
Top down plug.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/30/2011 10:30 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 238' w/245 sxs cement.  
5 1/2" production casing set at 4324' w/200 sxs cement.  
TD 4327'. DV Tool at 2014' w/400 sxs cement.  
Connected to 5 1/2" production casing - pumped 50 sxs cement mixed with 200# hulls - followed with 14 sxs gel and 245 sxs cement mixed with 300# hulls.  
Max. P.S.I. 1000#.  
Connected to 8 5/8" surface casing - pumped 10 sxs cement.  
Max. P.S.I. 200#.

Perfs:

Top	Bot	Thru	Comments
3953	3994		KC

Remarks: SWIFT CEMENTING COMPANY-TICKET #20464.

Plugged through: CSG

RECEIVED  
DEC 16 2011  
KCC WICHITA

District: 04

Signed

*Darrel Dipman*

(TECHNICIAN)

*12/22/11*

Form CP-2/3

DEC 08 2011