

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-10026-00-00  
Spot: SWNW Sec/Twnshp/Rge: 34-30S-8W  
3300 feet from S Section Line, 660 feet from W Section Line  
Lease Name: BOYLE K Well #: 2  
County: KINGMAN Total Vertical Depth: 4485 feet

Operator License No.: 33999  
Op Name: LINN OPERATING, INC.  
Address: 600 TRAVIS STE 5100  
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	290		300 SX
PROD	4.5	4484	1930	250 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/22/2011 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 425-1000

Proposed Plugging Method: SAND TO 4370' & 4 SKS. REC CASING, 35 SX 1200', 35 SX 700', CIRC 340'.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: NONE  
Date/Time Plugging Completed: 11/22/2011 2:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 4321' & CAPPED WITH 4 SKS. THE CASING WAS RECOVERED FROM 1930' & PULLED TO 1200' WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 700' WHERE 35 SX OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 340', WHERE CMT WAS CIRCD TO SURFACE WITH 115 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4420	4425	CSG	

Remarks: QUALITY WELL SERVICE 60/40 4%

Plugged through: CSG

District: 02

Signed \_\_\_\_\_

  
(TECHNICIAN)

RECEIVED  
DEC 16 2011  
KCC WICHITA  
Form CP-2/3  
12/23/11

JK