

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-00432-00-00  
Spot: SWSENE Sec/Twnshp/Rge: 5-30S-8W  
2310 feet from N Section Line, 990 feet from E Section Line  
Lease Name: POMEROY UNIT Well #: 1  
County: KINGMAN Total Vertical Depth: 4345 feet

Operator License No.: 33999  
Op Name: LINN OPERATING, INC.  
Address: 600 TRAVIS STE 5100  
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	4261		
SURF	8.625	290		
PROD	4.5	4344	1990	

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/23/2011 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 425-1000

Proposed Plugging Method: 35 SX 1300, 345 SX 800, CIRC 340'. SAND TO 4170 & 4 SKS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: NONE  
Date/Time Plugging Completed: 11/23/2011 6:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 4180' & 4 SKS CMT. THE CASING WAS RECOVERED FROM 1990' & PULLED TO 1300' WHERE 35 SKS CMT WAS SPOTTED. THE CASING WAS PULLED TO 800' WHERE 35 SX OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 340' WHERE CMT WAS CIRC'D TO SURFACE WITH 125 SKS CMT.

Perfs:

Top	Bot	Thru	Comments
4277	4280	CSG	
4224	4230	CSG	

Remarks: QUALITY WELL SERVICE 60/40 4% GEL

Plugged through: CSG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED

DEC 16 2011

Form CP-2/3

12/23/11

KCC WICHITA