

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-01152-00-00
Spot: SWNESW Sec/Twnshp/Rge: 24-30S-8W
1650 feet from S Section Line, 1650 feet from W Section Line
Lease Name: WEST SPIVEY UNIT Well #: 3
County: KINGMAN Total Vertical Depth: 4436 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	183		250 SX
L1	5	4436		160 SX
PROD	7	4311		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/21/2011 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (580) 237-6152

Proposed Plugging Method: SAND TO 4210 & 7 SKS

Plugging Proposal Received By: _____ Witness Type: NONE
Date/Time Plugging Completed: 10/21/2011 8:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 4210' & CAPPED WITH 7 SKS CMT. NO RECOVERY PERFORATED AT 1200', 700' & 250'. RAN TUBING TO 1200' SPOTTED 50 SX CMT. PULLED TUBING TO 700' & SPOTTED 50 SX CMT. PULLED CASING TO 250' AND CIRC'D CMT TO SURFACE UP BACKSIDE WITH 160 SKS CMT.

Perfs:

Top	Bot	Thru	Comments
4332	4338	CSG	
4285	4436	CSG	OHIO SQUEEZED

Remarks: QUALITY WELL SERVICE 60/40 4% GEL 3% CACL

Plugged through: TBG

District: 02

Signed _____

(TECHNICIAN)

RECEIVED

DEC 16 2011

Form CP-2/3

12/23/11

KCC WICHITA