

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-01151-00-00  
Spot: SWSESW Sec/Twnshp/Rge: 24-30S-8W  
385 feet from S Section Line, 1595 feet from W Section Line  
Lease Name: WEST SPIVEY UNIT Well #: 4  
County: KINGMAN Total Vertical Depth: 4415 feet

Operator License No.: 33999  
Op Name: LINN OPERATING, INC.  
Address: 600 TRAVIS STE 5100  
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	197		250 SX
PROD	5.5	4416		200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/24/2011 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (580) 237-6152

Proposed Plugging Method: SAND TO 4300' & 5 SKS CMT. PULL CASING 35 SX 1200', 35 SX 700', CIRC 250-0'.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: NONE  
Date/Time Plugging Completed: 10/25/2011 12:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

PERFORATED CASING AT 1200', 700' & 250'. RAN TUBING TO 1200' SPOTTED 35 SKS CMT. PULLED TUBING TO 700' SPOTTED 353 SX CMT. PULLED TUBING TO 250' AND PUMPED 50 SKS CMT. TIED ONTO 5 1/2 8 5/8 ANNUALS & PUMPED 65 SXD CMT. 10/25/11 CMT FELL TO 500'. TOPPED OFF FROM 250-0' THRU TUBING. RAN 1" TO 40' ON BACKSIDE & FILLED WITH CMT. 70 SKS CMT.

Perfs:

Top	Bot	Thru	Comments
4362	4372	CSG	

Remarks: QUALITY WELL SERVICE 60/40 4% GEL 3% CACL.

Plugged through: TBG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED  
DEC 16 2011  
KCC WICHITA  
Form CP-2/3  
12/23/11