

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-21932-00-00
Spot: SENWNEW Sec/Twnshp/Rge: 23-27S-34W
509 feet from N Section Line, 1904 feet from W Section Line
Lease Name: BRINKMAN Well #: D-1
County: HASKELL Total Vertical Depth: 5400 feet

Operator License No.: 5447
Op Name: OXY USA INC.
Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3980		WITH 2 SX CMT
CIBP		4388		WITH 2 SX CMT
SURF	8.625	1941		WITH 600 SX CMT
PROD	5.5	5399	2512	WITH 235 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/08/2011 12:00 PM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PLUG AT 1970' WITH 50 SX CMT. PLUG AT 800' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/08/2011 5:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

CIBP @ 4388' WITH 2 SX CMT. CIBP @ 3980' WITH 2 SX CMT. 1ST PLUG CIRCULATED HOLE WITH MUD & PUMPED 50 SX CMT AT 1970'. 2ND PLUG AT 800' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5168	5178		ST GENEVIEVE
5062	5068		MORROW
4438	4443		KC
4078	4088		LANSING

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

RECEIVED
DEC 14 2011
KCC DODGE CITY

Signed

Jack MacLaskey
(TECH)

RECEIVED

DEC 16 2011

KCC WICHITA

Form CP-28

12/23/11