

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-21051-00-02
Spot: SWSWSW Sec/Twnshp/Rge: 35-22S-34W
330 feet from S Section Line, 4950 feet from E Section Line
Lease Name: LOOMIS B Well #: 1
County: FINNEY Total Vertical Depth: 4950 feet

Operator License No.: 5447
Op Name: OXY USA INC.
Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3890		WITH 2 SX CMT
CIBP		4610		WITH 2 SX CMT
SURF	8.625	1970		WITH 725 SX CMT
COND	20	40		WITH 4.5 YDS CMT
DVT		3121		
PROD	5.5	4949	0	WITH 920 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/02/2011 1:30 PM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/02/2011 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 3890' WITH 2 SX CMT. 1ST PLUG AT 3150' WITH 25 SX CMT. 2ND PLUG AT 2000' WITH 25 SX CMT. 3RD PLUG AT 1100' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 5 SX CMT. ANNULUS FULL OF CMT. COULD NOT PUMP IN TO.

Perfs:

Top	Bot	Thru	Comments
4710	4716		ST LOUIS
4692	4698		MORROW
4376	4382		MARMATON
4152	4158		LANSING
4012	4018		LANSING
3909	3918		LANSING

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: TBG

RECEIVED
DEC 16 2011
KCC WICHITA

District: 01

RECEIVED

DEC -7 2011

KCC DODGE CITY

Signed

Ken Jehlik

(TECHNICIAN)

12/23/11