

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-22089-00-00
Spot: SESENWSW Sec/Twnshp/Rge: 35-25S-33W
1645 feet from S Section Line, 1275 feet from W Section Line
Lease Name: DRUSSEL H Well #: 1
County: FINNEY Total Vertical Depth: 5214 feet

Operator License No.: 5447
Op Name: OXY USA INC.
Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5080		WITH 2 SX CMT
SURF	8.625	1949		WITH 760 SX CMT
PROD	5.5	5512	2336	WITH 160 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/30/2011 10:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed
Plugging
Method:

PLUG AT ~~16980~~ ¹⁹⁸⁰ WITH 50 SX CMT. PLUG AT 950' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: JACK MACLASKEY WitnessType: PARTIAL
Date/Time Plugging Completed: 11/30/2011 3:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

CIBP ALREADY SET @ 5080' WITH 2 SX CMT. 1ST PLUG AT 1980' WITH 50 SX CMT.
2ND PLUG AT 950' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5116	5126		ST LOUIS

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

Signed

Jack MacLaskey
(TECHNICIAN)

RECEIVED
DEC -7 2011
KCC DODGE CITY

RECEIVED

DEC 16 2011

KCC WICHITA