

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-20994-00-00
Spot: NWNW Sec/Twnshp/Rge: 22-30S-8W
4620 feet from S Section Line, 4620 feet from E Section Line
Lease Name: LECKLIDER Well #: 1
County: KINGMAN Total Vertical Depth: 4260 feet

Operator License No.: 8740
Op Name: BRAMWELL PETROLEUM, INC.
Address: 15183 SW 25TH AVE
SPIVEY, KS 67142

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-------------|
| SURF | 8.625 | 326 | | 200 SXS CMT |
| PROD | 4.5 | 4259 | 2100 | 125 SXS CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/26/2011 8:00 AM
Plug Co. License No.: 34235 Plug Co. Name: AMIGOS WELL SERVICE INC.
Proposal Rcvd. from: DOUGLAS BRAMWELL Company: BPI Phone: (620) 532-6019

Proposed Plugging Method: SAND TO 4160 & 4 SKS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: NONE
Date/Time Plugging Completed: 10/27/2011 12:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 4220, 4224 & CAPPED WITH 4 SXS CMT. THE CASING WAS RECOVERED FROM 2100 & PULLED TO 1250' WHERE 35 SX OF CMT WAS SPOTTED. PULLED CASING TO 700' WHERE 35 SX OF CMT WAS SPOTTED. PULLED CASING TO 350' WHERE CMT WAS CIRCD TO SURFACE.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4220 | 4224 | CSG | |

Remarks: ALLIED CMT 60/40

Plugged through: CSG

District: 02

Signed _____

(TECHNICIAN)

RECEIVED

DEC 16 2011

KCC WICHITA

12/23/11
Form CP-2/3