

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-21810-00-00
Spot: NESW Sec/Twnshp/Rge: 9-33S-40W
1896 feet from S Section Line, 1952 feet from W Section Line
Lease Name: CNG Well #: 9 #1
County: MORTON Total Vertical Depth: 5950 feet

Operator License No.: 5278
Op Name: EOG RESOURCES, INC.
Address: 3817 NW EXPRESSWAY STE 500
OKLAHOMA CITY, OK 73112

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5426		WITH 10 SX CMT
CIBP		5700		
SURF	8.625	1698		WITH 480 SX CMT
DVT		3236		
PROD	5.5	5940	2000	WITH 356 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/06/2011 9:30 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @5426' WITH 10 SX CMT. PLUG AT 3300' WITH 20 SX CMT. PLUG AT 1728' WITH 100 SX CMT. PLUG AT 650' WITH 60 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: PARTIAL
Date/Time Plugging Completed: 12/05/2011 3:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

SET CIBP @ 5410' WITH 20 SX CMT. 1ST PLUG AT 3300' WITH 20 SX CMT TO COVER DV TOOL. 2ND PLUG AT 1730' WITH 100 SX CMT. LET CMT SET 2 HOURS. TAGGED TOC @ 1430'. 3RD PLUG AT 650' WITH 60 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5784	5800		MORROW
5476	5497		MORROW

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

RECEIVED
DEC 14 2011
KCC DODGE CITY

Signed

Jack MacLaskey
(TECHNICIAN)

RECEIVED
DEC 16 2011

KCC WICHITA

Form CR-213

12/23/11