

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-22185-00-00
Spot: N2SESENE Sec/Twnshp/Rge: 7-32S-34W
2289 feet from N Section Line, 332 feet from E Section Line
Lease Name: HL&C Well #: 7 #1
County: SEWARD Total Vertical Depth: 6350 feet

Operator License No.: 5278
Op Name: EOG RESOURCES, INC.
Address: 3817 NW EXPRESSWAY STE 500
OKLAHOMA CITY, OK 73112

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5508		WITH 5 SX CMT
CIBP		6012		
CIBP		6111		
SURF	8.625	1717		WITH 500 SX CMT
PROD	4.5	6347	2517	WITH 245 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/30/2011 8:30 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 5512'. PLUG AT 1750' WITH 80 SX CMT. PLUG AT 610' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/30/2011 12:00 PM KCC Agent: JACK MACCLASKEY

Actual Plugging Report:

SET CIBP @ 5508' WITH 5 SX CMT. 1ST PLUG AT 1762' WITH 80 SX CMT. 2ND PLUG AT 600' WITH 60 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6120	6150		Chester
6079	6084		Chester
6062	6072		Chester
5562	5572		Morrow

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

RECEIVED

DEC -7 2011

KCC DODGE CITY

Signed

Jack L MacClaskey
(TECHN)

RECEIVED

DEC 16 2011

KCC WICHITA

Form CP 213