

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-22207-00-01
Spot: NENESWSW Sec/Twnshp/Rge: 11-33S-35W
1283 feet from S Section Line, 1236 feet from W Section Line
Lease Name: ALDERMAN UNIT Well #: 3
County: STEVENS Total Vertical Depth: 2954 feet

Operator License No.: 5208
Op Name: EXXONMOBIL OIL CORP
Address: 14950 HEATHROW FORREST PKWY P
HOUSTON, TX 77210

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2660		WITH 5 SX CMT
SURF	8.625	660		WITH 375 SX CMT
PROD	5.5	2944	784	WITH 300 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/09/2011 8:30 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 2660' WITH 2 SX CMT. PLUG AT 1680' WITH 30 SX CMT. PLUG AT 690' WITH 100 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE
Date/Time Plugging Completed: 12/09/2011 2:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 2660' WITH 5 SX CMT. 1ST PLUG AT 1680' WITH 30 SX CMT. SHOT 5 1/2" @ 1090'. UNABLE TO PULL. RESHOT 5 1/2" @ 784'. POH W/CSG. 2ND PLUG AT 784' WITH 140 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2860	2910		
2810	2847		
2760	2778		
2710	2725		

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
DEC 14 2011
KCC DODGE CITY

12/23/11

RECEIVED
DEC 16 2011
KCC WICHITA