

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-20370-00-00
Spot: SWNWSNW Sec/Twnshp/Rge: 17-32S-36W
1714 feet from N Section Line, 1390 feet from W Section Line
Lease Name: RATCLIFF Well #: 1-2
County: STEVENS Total Vertical Depth: 3065 feet

Operator License No.: 5208
Op Name: EXXONMOBIL OIL CORP
Address: 14950 HEATHROW FORREST PKWY P
HOUSTON, TX 77210

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	619		WITH 300 SX CMT
PROD	5.5	3065	1425	WITH 400 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/21/2011 2:30 PM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: WELL HAS FILL TO 2433'. PUMP 100 SX CMT AT 2400'. SHOOT 5 1/2" CASING & POH. RIH WITH TBG TO 650' & SPOT 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: PARTIAL
Date/Time Plugging Completed: 11/21/2011 4:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

11/18/11: TAGGED TOP OF FILL AT 2433'. PUMPED 100 SX CMT AT 2430'. SIFN.
11/21/11: TAGGED TOC @ 1586'. SHOT 5 1/2" CASING AT 1425'. POOH. RIH W/TBG TO 650' & PUMPED 75 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2981	2984		
2977	2979		
2957	2966		
2942	2945		
2934	2938		

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed

Jack MacLaskey
(TECHNICIAN) 12/23/11

RECEIVED
DEC -7 2011
KCC DODGE CITY

RECEIVED
DEC 16 2011
KCC WICHITA