

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-093-20503-00-00
Spot: SESENW Sec/Twnshp/Rge: 4-26S-35W
3095 feet from S Section Line, 2196 feet from W Section Line
Lease Name: WILLIAM T GILDART GAS LN Well #: 2
County: KEARNY Total Vertical Depth: 2941 feet

Operator License No.: 5208
Op Name: EXXONMOBIL OIL CORP
Address: 14950 HEATHROW FORREST PKWY P
HOUSTON, TX 77210

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2864		
SURF	8.625	783		WITH 400 SX CMT
PROD	5.5	2940	1082	WITH 350 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/22/2011 1:00 PM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RENE Company: ORR ENTERPRISES, INC. Phone: (580)251-9618

Proposed Plugging Method: PLUG AT 2878' WITH 50 SX CMT. PLUG AT 1950' WITH 30 SX CMT. PLUG AT 810' WITH 75 SX CMT. PLUG AT 60' WITH 25 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/28/2011 11:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

1ST PLUG TAGGED OBSTRUCTION IN 5 1/2" CASING WITH TBG AT 2110'. SPOT 65 SX CMT PLUG AT 2110'. (NO CIRCULATION). TAG TOC W/TBG @ 2040'. 2ND PLUG AT 2040' WITH 65 SX CMT. TAG TOC W/WIRELINE AT 1510'. 3RD PLUG AT 810' WITH 75 SX CMT. 4TH PLUG AT 62' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2869	2878		
2853	2855		
2837	2844		
2827	2839		
2821	2824		

Remarks: USED CLASS C CEMENT W/2% GEL BY ORR ENTERPRISES.

Plugged through: TBG

RECEIVED

DEC 16 2011

KCC WICHITA

District: 01

Signed

Ken Jehlik

(TECHNICIAN)

RECEIVED

DEC -7 2011

KCC DODGE CITY

✓ 12/23/11

Form CP 2/3