

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-00602-00-01
Spot: NENWSWNE Sec/Twnshp/Rge: 14-13S-17W
1650 feet from N Section Line, 2110 feet from E Section Line
Lease Name: KARLIN Well #: 1
County: ELLIS Total Vertical Depth: 3568 feet

Operator License No.: 33905
Op Name: ROYAL DRILLING INC
Address: 719 WITT AVE PO BOX 342
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	167	0	125 SX
PROD	5.5	3538	0	125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/12/2011 2:30 PM
Plug Co. License No.: 33905 Plug Co. Name: ROYAL DRILLING INC
Proposal Rcvd. from: JOHN L DRISCOLL Company: ROYAL DRILLING INC Phone: (785) 483-6220

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel.
Rods and tubing at 1262' - over shot in hole.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/12/2011 4:40 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Shot off overshot at 1200'.
Allied rigged to tubing and pumped 119 sxs to circulate cement to surface.
Pulled tubing - rigged to 5 1/2" casing with a swedge and pumped 25 sxs cement.
Max. P.S.I. 300#. S.I.P. 300#.
Rigged to 8 5/8" casing - pumped 60 sxs cement.
Max. P.S.I. 100#. S.I.P. 50#.

Perfs:

Top	Bot	Thru	Comments
3358	3365		
3343	3363		

Remarks: ALLIED CEMENTING COMPANY-TICKET #35186.

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

CM

RECEIVED

DEC 19 2011

Form CP-2/3

KCC WICHITA

12/23/11

DEC 15 2011