

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-03532-00-00
Spot: NESENW Sec/Twnshp/Rge: 11-15S-14W
3647 feet from S Section Line, 3069 feet from E Section Line
Lease Name: FLEGLER B Well #: 5
County: RUSSELL Total Vertical Depth: 3247 feet

Operator License No.: 31369
Op Name: GINTHER, KELLY DBA KAY DEE OIL
Address: 112 CINDY DR
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	3200	0	w/unknown sxs cmt
COND	10.75	805		800 SX
PROD	5.5	3241	0	175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/12/2011 9:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: KELLY GINTHER Company: KAY DEE OIL Phone: (785) 483-5508

Proposed Squeeze from 700' to 2600' with 250 sxs cement.
Plugging Tubing stacked out at 580' - solid.
Method: Pulled tubing out - plugged down casing.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/12/2011 2:15 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied onto casing - pumped 250 sxs cement with 200# hulls - ran out of cement - ordered more cement.
Pumped 100 sxs cement - ran out again - ordered more cement.
Pumped another 100 sxs cement with 300# hulls - top would not fill up.
Shut down - waited 1 1/2 hours and pumped another 75 sxs cement - full.


Perfs:

Top	Bot	Thru	Comments
3194	3199		LKC K
3170	3173		LKC J
2999	3003		LKC B
2934	2939		TORONTO
2866	2872		TOPEKA

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #545.

Plugged through: CSG

District: 04

Signed 
(TECHNICIAN)

CM

RECEIVED Form CP-2/3
DEC 19 2011 12/23/11

DEC 15 2011

KCC WICHITA