

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-165-21743-00-00  
Spot: NESESW Sec/Twnshp/Rge: 14-16S-20W  
853 feet from S Section Line, 2621 feet from W Section Line  
Lease Name: STULL-ELLIOTT Well #: 1  
County: RUSH Total Vertical Depth: 3950 feet

Operator License No.: 34004  
Op Name: SAXON OIL COMPANY  
Address: 11111 KATY FWY #900  
HOUSTON, TX 77079

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3810		WITH 2 SX CMT
SURF	8.625	219		WITH 150 SX CMT
PC		1400		200 SX
PROD	5.5	3947	0	WITH 150 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/05/2011 10:00 AM  
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING  
Proposal Rcvd. from: MARK BIEKER Company: SAXON OIL Phone: (785) 261-1876

Proposed Plugging Method: SET CIBP @ 3810' & 2 SX CMT. RUN TBG TO 1400' & CIRCULATE CMT TO SURFACE. PRESSURE TEST 8 5/8" X 5 1/2" ANNULUS TO 500 PSIG WITH CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: PARTIAL  
Date/Time Plugging Completed: 12/06/2011 10:25 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 3810' WITH 2 SX CMT ON TOP WITH DUMP BAILER. PRESSURED 8 5/8" X 5 1/2" ANMULUS TO 1000 PSIG WITH 10 SX CMT. RAN TBG TO 1428'. PUMPED 290 SX CMT DOWN TBG AND NEVER HAD ANY RETURNS UP THE 5 1/2". 12/6/11: TAGGED CMT INSIDE 5 1/2" @ 897'. PULLED TBG TO 868' & CIRCULATED CMT TO SURFACE. PULLED TBG OUT OF HOLE & PRESSURED 5 1/2" TO 250 PSIG. TOTAL OF 95 SX CMT TO FILL FROM 897' TO 0'.

Perfs:

Top	Bot	Thru	Comments
3866	3870		

RECEIVED  
DEC 21 2011  
KCC WICHITA

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA LACK OF LEASE\*\* USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

Signed

*Richard M. Lacey*

(TECHNICIAN)

RECEIVED

DEC 12 2011

KCC DODGE CITY

12/23/11

Form CP-2/3