

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-30035-00-00
Spot: NWSESW Sec/Twnshp/Rge: 6-19S-7W
737 feet from S Section Line, 3414 feet from E Section Line
Lease Name: WRIGHT A Well #: 1
County: RICE Total Vertical Depth: 3344 feet

Operator License No.: 5610
Op Name: BRUCE OIL COMPANY, L.L.C.
Address: 1704 LIMESTONE RD
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	3226		
SURF	8.625	201		200 SX
PROD	4.5	3379		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/13/2011 3:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 12/13/2011 6:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:
MIRU, CK BOTTOM. SAND PERFS TO 3130' AND CAP WITH 4 SX'S CEMENT.
ATTEMPT TO CUT CASING--COULD NOT. PERFORATE AT 1050' AND PUMP 35 SX'S
CEMENT WITH 3% CC. HAVE PERFORATORS CUT CASING AT 834'. PULL CASING
UP TO 700' AND PUMP 35 SX'S CEMENT WITH 3% CC AND 100#'S COTTON HULLS.
PULL CASING TO 250' AND CIRCUALTE CEMENT TO SURFACE. PULL CASING ON
OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3329	3336	CSG	
3182	3184	CSG	

RECEIVED
DEC 21 2011
KCC WICHITA

Remarks: DENIED TA--HFLD. QUALITY WELL CEMENT TICKET #5339. LOG TECH #36316.
Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

Form CP-2/3
12/23/11

JK