

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-11042-00-01
Spot: NENWSW Sec/Twnshp/Rge: 35-25S-12W
2302 feet from S Section Line, 4302 feet from E Section Line
Lease Name: SLADE Well #: 2
County: STAFFORD Total Vertical Depth: 4255 feet

Operator License No.: 32457
Op Name: ABERCROMBIE ENERGY, LLC
Address: 10209 W. CENTRAL, STE 2
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3562		WITH 2 SX CMT
SURF	8.625	364		WITH 370 SX CMT
PROD	5.5	4252	894	WITH 200 SX CMT

Well Type: SWD UIC Docket No: D14624.0 Date/Time to Plug: 12/07/2011 12:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP @ 3680' & 2 SX CMT. PLUG AT 700' WITH 15 SX GEL & 50 SX CMT. PLUG AT 390' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/07/2011 2:45 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PACKER FISH IN HOLE @ 3638' & 4050 SET CIBP @ 3562' & 2 SX CMT ON TOP WITH DUMP BAILER. 1ST PLUG AT 710' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 383' WITH 50 SX CMT. 3RD PLUG AT 62' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4061	4083		VIOLA
3638	3689		LANSING

RECEIVED
DEC 21 2011
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED
DEC 12 2011
KCC DODGE CITY

Signed

Richard W. Lacey
(TECHNICIAN)

12/23/11
Form CP-2/3

cc to AIC 12/21/11