

1080264

TO: STATE CORPORATION COMMISSION

9-17

API NUMBER 15-171-20,349-00-01  
SW SW SE SEC. 23, T 17 S, R 31 W

CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2310 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME BROWER OWWO WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY SCOTT

OPERATOR LICENSE # 31251

WELL TOTAL DEPTH 4610 FEET <sup>149.83</sup>

OPERATOR: WABASH ENERGY CORPORATION PRODUCTION CSG: SIZE 4 1/2" @ 4600' WITH 175 SX

NAME AND ADDRESS PO BOX 595 SURFACE CASING: SIZE 8 5/8" @ 279' WITH 150 SX

ADDRESS LAWRENCEVILLE, IL 62439

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD WELL  D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SWIFT SERVICES INC LICENSE NUMBER 32382

ADDRESS PO BOX 466, NESS CITY, KS 67560

COMPANY TO PLUG AT: HOUR: 1:30 PM DAY: 17 MONTH: 09 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM

(COMPANY NAME) SWIFT SERVICES INC (PHONE) 785-798-2300

WERE: PERFS AT 3532-34, 4272-75, 4304-10, & 4541-46 DV TOOL @ 2200' WITH 200 SX CEMENT

PUMP DOWN 8 5/8" X 4 1/2" ANNULUS 5 SX CEMENT. PRESSURED UP TO 500# SHUT IN. PUMPED DOWN 4 1/2"

CASING 300# HULLS STARTED MIXING CEMENT WITH 400# HULLS MIXED IN. PUMPED TOTAL OF 255

SX CEMENT. MAXIMUM PSI 800#. SHUT IN WITH 500#.

INVOICED

DATE 10-11-99 PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

INV. NO. 60674

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL  PART  NONE

OPERATIONS COMPLETED: HOUR: 2:30 PM DAY: 17 MONTH: 09 YEAR: 1999

ACTUAL PLUGGING REPORT

PUMPED DOWN 8 5/8" X 4 1/2" ANNULUS 5 SX CEMENT. PRESSURED UP TO 500# SHUT IN. PUMPED DOWN 4 1/2"

CASING 300# HULLS STARTED MIXING CEMENT WITH 400# HULLS MIXED IN. PUMPED TOTAL OF 255

SX CEMENT. MAXIMUM PSI 800#. SHUT IN AT 500#.

RECEIVED STATE CORPORATION COMMISSION

001 - 6 1999

REMARKS: USED 65/35 POZMIX 8% GEL BY SWIFT SERVICES. NO CASING RECOVERED. (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Kevin P. Strube (TECHNICIAN) FORM CP-2/3

Handwritten initials and a large circled 'P' at the bottom right of the page.