

1 060522

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 171-20,291-00-00

C S/2 NW SE, SEC. 20, T 17 S, R 31 W/X

1650 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9937

Lease Name Boyer Well # 20-10

Operator: Mallon Oil Company
Name & Address: 1616 Glenarm Place, Suite 2850
Denver, CO 80202

County Scott 154.38

Well Total Depth 4750 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 304

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Co. License Number 6033

Address 250 North Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 7:00 am Day: 23 Month: March Year: 19 85

Plugging proposal received from Terry McRae

(company name) Murfin (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2290' with 50 sx cement

2nd plug at 1350' with 50 sx cement

3rd plug at 330' with 50 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 8:30 am Day: 23 Month: March Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2290' with 50 sx cement, 2nd plug at 1350' with

50 sx cement, 3rd plug at 330' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole

with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

RECEIVED STATE CORPORATION COMMISSION

MAR 28 1985

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun

(If additional description is necessary, use BACK of this form.) Kansas

INVOICED

I (XXX) / did not) observe this plugging.

Signed Paul A. Luthi (TECHNICIAN)

DATE 4-3-85

INV. NO. 7510 3-23 APR 26 1985

JUN 12 1985

AUG 23 1985 SF

FORM CP-2/3 Rev. 01-84