

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20291-00-01
Spot: S2NWSE Sec/Twnshp/Rge: 20-17S-31W
1650 feet from S Section Line, 1980 feet from E Section Line
Lease/Unit Name: BROOKOVER Well Number: 7-20
County: SCOTT Total Vertical Depth: 4038 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

Production Casing Size: 5.5 feet: 4031 WITH 675 SX CMT
Surface Casing Size: 8.625 feet: 304 WITH 200 SX CMT

#13124

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/23/2003 8:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: WAYNE GERSTNER Company: BEREXCO Phone: (620) 772-1155

Proposed Plugging Method: SQUEEZE PERFS 2970-83' & OPEN HOLE 4031-38 WITH 100 SX CMT. CIRCULATE CMT IN 5 1/2" TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: KEVIN STRUBE WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/23/2003 3:45 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 4038'. DV @ 2290'. PERFS AT 3979-83'. OPEN HOLE FROM 4031-38'. RAN PACKER TO 3761'. SQUEEZE PERFS & OPEN HOLE WITH 50 SX CLASS A CMT WITH 2% CC & 50 SX CLASS A CMT TO 1000#. TOC AT 3761'. PULLED TUBING & PACKER, RAN BACK IN HOLE TO 2305'. CIRCULATED 5 1/2" WITH 200 SX CMT. PULLED TUBING OUT OF HOLE. TOPPED OFF WITH 25 SX CMT. PUMPED DOWN 8 5/8" X 5 1/2" ANNULUS WITH 10 SX CMT. PRESSURED UP TO 500# & SHUT IN.

RECEIVED
OCT 31 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: TBG

District: 01

RECEIVED
OCT 27 2003
KCC Dodge City

Signed

Kevin D Strube

(TECHNICIAN)

INVOICED
DATE 10-31-03
INV. NO. 2004060714

Form CP 2/32