

1 010213

JAN 6 1987

234 R

API NUMBER 15- 171-20,350 -00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SW NE SE, SEC. 19, T 17 S, R 31 W/R

1650 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9421

Lease Name See Well # 1-19

Operator: Boger Brothers Drilling, Inc.  
Name & Address: P.O. Box 723  
Great Bend, KS 67530

County Scott 134 94

Well Total Depth 4152 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 311

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A  X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Boger Brothers Drilling, Inc. License Number 9421

Address P.O. Box 723, Great Bend, KS 67530

Company to plug at: Hour: 3 p.m. Day: 6 Month: 1 Year: 19 87

Plugging proposal received from Walt Meharg

(company name) Boger Brothers Drilling, Inc. (phone) 316-792-8151

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2311-33'

1st plug at Base Anhydrite with 50 sx cement, 2nd plug at 1500' with 100 sx cement,

3rd plug at 30' below base of surface pipe with 50 sx cement,

4th plug at 0-40' with 10 sx cement, 5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None  X

Operations Completed: Hour: 7:45 p.m. Day: 6 Month: 1 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 2311' with 50 sx cement,

2nd plug at 1500' with 100 sx cement,

3rd plug at 340' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

STATE CORPORATION COMMISSION

02-09-87

FEB 9 1987

CONSERVATION DIVISION  
Wichita, Kansas

Signed [Signature] (TECHNICIAN)

DATE 2-9-87

INV. NO. 16094 FEB 10 1987

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 1 29 87 month day year

API Number 15-17-20,350-00-00

OPERATOR: License # 9421 Name BOGER BROTHERS DRILLING, INC. Address P.O. Box 723 City/State/Zip Great Bend, KS 67530 Contact Person Steve Mitchell Phone 316/792-8151

SW NE SE Sec. 19 Twp. 17 S, Rg. 31 X West 1650 Ft. from South Line of Section 990 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 330 feet County Scott

CONTRACTOR: License # UNKNOWN Name Boger Brothers City/State

Lease Name SEE Well # 1-19

Well Drilled For: X Oil SWD Infield X Mud Rotary Gas Inj X Pool Ext Air Rotary OWWO Expl Wildcat Cable

Ground surface elevation feet MSL Domestic well within 530 feet yes X no Municipal well within one mile: yes X no

Depth to bottom of fresh water 200 Depth to bottom of usable water 1500

Surface pipe by Alternate: 1-2 X Surface pipe planned to be set 220 min

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

Conductor pipe required Projected Total Depth 4500

Formation M155

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. Date Signature of Operator or Agent Steve Mitchell Title No

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required 220 feet per Alt. 1 2 This Authorization Expires 6-12-87 Approved By 12-12-86

Set 220 of 8 5/8 on 1/31/87

SW NE SE Sec. 19 Twp. 17 S, Rg. 31 X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 0-350' feet depth with continuous 10' SXS of 60/40 0.90 gel all water formations 30' below top of 50' in length 50' SXS of 2nd plug @ Top of Mississippi 1500' feet depth with 50' in length 100' SXS of 3rd plug @ top of Arbuckle Any feet depth with 50' in length 50' SXS of 4th plug @ top of Arbuckle Any feet depth with 50' in length 50' SXS of 5th plug @ feet depth with SXS of (2) Rathole with 1.5' SXS (b) Mousehole with SXS

PUSHER TD 4152 FORMATION Arbuckle Kc SURFACE PIPE 8 5/8 @ 2 1/4 ANHYDRITE 2311-3-ELEVATION STARTING TIME & DATE 1-6-87 COMPLETION TIME & DATE 5:00 7:45 - 1-6-87 1st PLUG @ Arb. FT. W/ 50 SX 2nd PLUG @ 1500 FT. W/ 100 SX 3rd PLUG @ 340 FT. W/ 50 SX 4th PLUG @ 40 FT. W/ 10 SX RAT HOLE CIRCULATED W/ 15 SX MOUSE HOLE CIRCULATED W/ SX WATER WELL PLUGGED W/ 10 CEMENT COMPANY H.C. 11,6, Kc TECHNICIAN

STATE CORPORATION COMMISSION FEB 9 1987 CONSERVATION DIVISION Wichita, Kansas