

2-15-88

To: 1 061066
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 171-20,055 -00-00
250' S SW
NE NW, SEC. 19, T 17 S, R 31 W/E
4040 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5245

Operator: Okmar Oil Company
Name &
Address 970 Fourth Financial Center
Wichita, KS 67202

Lease Name See "A" Well # 1

County Scott 136.05

Well Total Depth 4186 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 299

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Plains, Inc. License Number 4072

Address P.O. Box 346, Ness City, KS 67560

Company to plug at: Hour: 11:30 a.m. Day: 15 Month: 2 Year: 19 88

Plugging proposal received from Bob Grant

(company name) Okmar Oil Company (phone) 316-265-3311

were: 5 1/2" at 4097' PBD 3983' Perfs at 3970-75, 4023-30' Well squeezed at 1785' w/135 sx
1st plug pump 200 lbs. hulls, 20 sx gel, and 20 sx cement,
2nd plug pump through tubing .

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 p.m. Day: 15 Month: 2 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped 20 sx gel, 4 sx hulls, and 20 sx cement at 3930',

2nd plug pumped 20 sx cement at 2327', Pumped plugs through tubing.

3rd plug pumped 30 sx cement at 1424',

4th plug pumped 20 sx cement at 463',

5th plug pumped 10 sx cement at 60-0',

6th plug pumped 110 sx cement down 8 5/8" annulus. Shut in pressure at 250 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. No casing recovery.
(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
02-19-88
FEB 19 1988
CONSERVATION DIVISION
WICHITA, KANSAS

INVOICED

(did / ~~did not~~) observe this plugging.

Signed Paul A. Luthi
(TECHNICIAN)

DATE 2-22-88

INV. NO. 19908
2-15