

1 120252

5-5

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 171-20,385-00-00  
App. C SW NW, SEC. 16, T 17 S, R 31 W 1/4  
3240 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 3988  
Operator: Slawson Exploration Company, Inc.  
Name & Address: 104 South Broadway  
Wichita, KS 67202

Lease Name Rodenberg "K" Well # 1  
County Scott 151.45  
Well Total Depth 4660 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 350

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor L.D. Drilling License Number 6039  
Address RR 1, Box 183 B, Great Bend, KS 67530

Company to plug at: Hour: 11:30 p.m. Day: 4 Month: 5 Year: 19 89

Plugging proposal received from Greg Davidson  
(company name) L.D. Drilling (phone) 316-793-3051

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2946'  
Anhydrite 2299-2318'  
1st plug at 2320' with 50 sx cement, 2nd plug at 1460' with 80 sx cement,  
3rd plug at 380' with 50 sx cement,  
4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Duane Rankin  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 1:15 a.m. Day: 5 Month: 5 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 2320' with 50 sx cement,  
2nd plug at 1460' with 80 sx cement,  
3rd plug at 380' with 50 sx cement,  
4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 9 1989  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
did not observe this plugging.

DATE 5-10-89  
INV. NO. 24743

Signed Duane Rankin  
(TECHNICIAN)

FORM MUST BE TYPED  
FORM C-1 12/88

State of Kansas  
NOTICE OF INTENTION TO DRILL

FORM MUST BE SIGNED  
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

APPROX-

Expected Spud Date ... April ... 25 ... 1989 ...  
month day year

C-SW-NW Sec 16, Twp 17 S, Rg 31 East West

OPERATOR: License # 3988  
Name: SLANSON EXPLORATION COMPANY, INC.  
Address: 104 South Broadway  
City/State/Zip: Wichita, Kansas 67202  
Contact Person: Jim Rensberg  
Phone: (316) 263-3201

3240' feet from South line of Section  
4620' feet from East line of Section  
(Note: Locate well on Section Plat Below)

CONTRACTOR: License #: 6039  
Name: L.D. Drilling, Inc.

County: Scott  
Lease Name: Rodenberg, "K" Well #: 1  
Field Name: Wildcat

Well Drilled for: Well Class: Type Equipment:  
X Oil ... Inj ... Infield X Mud Rotary  
... Gas ... Storage ... Pool Ext. ... Air Rotary  
... OAWO ... Disposal X Wildcat ... Cable  
... Seismic; ... # of Holes

Is this a Prorated Field? ... yes X no  
Target Formation(s): Mississippian  
Nearest lease or unit boundary: 660'  
Ground Surface Elevation: 2946' GR feet MSL

If OAWO: old well information as follows:  
Operator:  
Well Name:  
Comp. Date: Old Total Depth

Domestic well within 330 feet: ... yes X no  
Municipal well within one mile: ... yes X no  
Depth to bottom of fresh water: 180'  
Depth to bottom of usable water: 1350'  
Surface Pipe by Alternate: 1 X 2  
Length of Surface Pipe Planned to be set: 350'

Directional, Deviated or Horizontal wellbore? ... yes X no  
If yes, total depth location:

Length of Conductor pipe required: None  
Projected Total Depth: 4650'  
Formation at Total Depth: Mississippian  
Water Source for Drilling Operations: Irrigation well  
... well ... farm pond ... other

DWR Permit #: 00697400A  
Will Cores Be taken? ... yes X no  
If yes, proposed zone:

200' Alt. II Req.


Spud 4-26-89 6:00 PM  
350-848

PUSHER Co Rig #1000  
1720' 8 1/2" Wildcat, CR  
TD Wildcat FORMATION Miss  
SURFACE PIPE 8 7/8 @ 350  
ANHYDRITE 2259-2318 ELEVATION 2946  
STARTING TIME & DATE 11:30 AM 5-4-89  
COMPLETION TIME & DATE 1:15 AM 5-5-89

1st PLUG @ 2320 FT. W/ 5/8 SX  
2nd PLUG @ 1460 FT. W/ 5/8 SX  
3rd PLUG @ 380 FT. W/ 5/8 SX  
4th PLUG @ 40 FT. W/ 1/2 SX  
RAT HOLE CIRCULATED W/ 1 1/2 SX  
MOUSE HOLE CIRCULATED W/ SX  
WATER WELL PLUGGED W/ SX

CEMENT COMPANY filled  
TECHNICIAN Rensberg, D.G.  
60-40-690

CONSERVATION DIVISION  
Wichita, Kansas  
MAY 9 1989  
Agent:



CONSERVATION DIVISION  
Wichita, Kansas

Spud date: \_\_\_\_\_

- REMEMBER TO:
- File Drill Pit Application (form CDP-1) with Intent to Drill;
  - file Completion form ACO-1 within 120 days of spud date;
  - file acreage attribution plat according to field proration orders;
  - Notify appropriate district office 48 hours prior to workover or re-entry;
  - Submit plugging report (CP-4) after plugging is completed;
  - Obtain written approval before disposing or injecting salt water.