

1 070199

70R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 171-20,335-00-00

NE SE SW, SEC. 14, T 17 S, R 31 W

990 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name Sharp 'N' Well # 1

Operator: Slawson, Donald C.

County Scott

Name & Address

200 Douglas Bldg.

Well Total Depth 4625 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 383

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Slawson Drilling Co., Inc. License Number 5657

Address 200 Douglas Bldg., Broadway & Douglas, Wichita, KS 67202

Company to plug at: Hour: 3:00 am Day: 12 Month: July Year: 1986

Plugging proposal received from Bob Rowe

(company name) Slawson Drilling Co., Inc. (phone) 316-263-3201

were: 1st plug spotted at 2300' with 50 sx cement Elevation 2912'

Anhydrite 2270'

2nd plug spotted at 1400' with 100 sx cement

3rd plug spotted at 400' with 40 sx cement

4th plug spotted from 40-0' with sx cement

5th plug to circulate rat hole with 15 sx cement. Cement to be used 60/40 Poz

with 3% Gel. Plugging Proposal Received by Dan Goodrow

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 6:00 am Day: 12 Month: July Year: 1986

ACTUAL PLUGGING REPORT 1st plug spotted at 2302' with 50 sx cement, 2nd plug spotted

at 1400' with 100 sx cement, 3rd plug spotted at 400' with 40 sx cement, 4th plug

spotted from 40-0' with 10 sx cement, 5th plug to circulate rat hole with 15 sx

cement.

RECEIVED
STATE CORPORATION COMMISSION
CONS. DIV. WICHITA, KS

JUL 18 1986

Remarks: Used 60/40 Poz with 3% Gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED

(did not) observe this plugging.

DATE 7-21-86

Signed Dan Goodrow (TECHNICIAN)

INV. NO. 14411

7-12