

1 050764

254 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C SW NW SW , SEC. 10 , T 17 S, R 31 W EX
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 171-20,310-00-00
1650 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5393

Lease Name Socolofsky Well # 1
County Scott 151.45
Well Total Depth 4660 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 387

Operator: A. L. Abercrombie, Inc.
Name & Address 801 Union Center
Wichita, KS 67202

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:00 am Day: 17 Month: February Year: 19 86

Plugging proposal received from Billy Fulls
(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 4659' PBDT 4530' Perfs at 4513-18' Port Collar at 1606'
1st plug sand back to 4460' and dump 5 sx cement on top of sand through bailer
2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 15 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 11:45 am Day: 17 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4460' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 15 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

Maximum pressure 600 psi and shut in 100 psi

Remarks: Recovered 2876' 5 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (did / ~~did not~~) observe this plugging.
DATE FEB 26 1986

RECEIVED
STATE CORPORATION COMMISSION

Signed Richard W. Lacey (TECHNICIAN)

FEB 24 1986

INV. NO. 12671

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84