

1 070907

1-16

180P

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-071-20,535-00-00
App. W/2 NW SW SEC. 26, T 20 S, R 42 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

2100 feet from S section line

4950 feet from E section line

Operator: Marathon Oil Company

Lease Name Spears Well # 1

Name & Address

County Greeley 175.50

P.O. Box 2690

Well Total Depth 5400 feet

Cody, WY 82414

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 483

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Company License Number 6033

Address 250 N. Water, Ste. 300, Wichita, KS 67202

Company to plug at: Hour: 4 a.m. Day: 16 Month: 1 Year: 19 91

Plugging proposal received from Tom Brock

(company name) Murfin Drilling Company (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2347-2400'

1st plug at 2400' with 50 sx cement, 2nd plug at 1400' with 50 sx cement,

3rd plug at 500' with 50 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 7 a.m. Day: 16 Month: 1 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 5250' with 50 sx cement,

2nd plug at 2400' with 50 sx cement,

3rd plug at 1400' with 50 sx cement,

4th plug at 500' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement, 7th plug to circulate mousehole with 10
sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(if additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
01-25-91
JAN 25 1991
CONSERVATION DIVISION
WICHITA, KANSAS

INVOICED (XXXX) did not observe this plugging.

Signed Dan Goodrow
(TECHNICIAN)

DATE FEB 12 1991

INV. NO. 30701
1-16 MAR 07 1991