

1070072

TO:

6-2

API NUMBER 15-071-20,685-00-00

STATE CORPORATION COMMISSION 110'E & 110'S of
NW NW NW, SEC. 23, T 20 S, R 42 W

CONSERVATION DIVISION - PLUGGING SECTION 440 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 440 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME Siverson WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY Greeley

OPERATOR LICENSE # 32283 WELL TOTAL DEPTH 2414 78.46 FEET

OPERATOR: Western Operating Company PRODUCTION CSG: SIZE _____ FEET _____

NAME AND 518 - 17th St. Suite 1680 SURFACE CASING: SIZE 8 5/8" FEET 628'

ADDRESS Denver, Co 80202

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD WELL _____ D/A X

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR Murfin Drilling Company LICENSE NUMBER 30606

ADDRESS P.O. Box 661, Colby, Kansas 67701-0661

COMPANY TO PLUG AT: HOUR: 5:00a.m. DAY 2 MONTH: 6 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM Bernie Meyer

(COMPANY NAME) Murfin Drilling Company (PHONE) (913)462-7541

WERE: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1350' with 100sx cement, 2nd plug at 650' with 50 sx cement

3rd plug at 120' with 10 sx cement, 4th plug at 40-0'with 10 sx cement

5th plug to circulate rathole with 15 sx cement

6th plug to circulate mousehole with 10 sx PLUGGING PROPOSAL RECEIVED BY Scott Alberg

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL _____ PART _____ NONE X

OPERATIONS COMPLETED: HOUR: 12:05 p.m. Day: 2 MONTH: 6 YEAR: 1998

ACTUAL PLUGGING REPORT 1st plug at 1350' with 100 sx

2nd plug at 650' with 50 sx, 3rd plug at 120' with 10 sx

4th plug at 40' with 10 sx,

5th plug to circulate rathole with 15 sx cement

6th plug to circulate mousehole with 10 sx cement

REMARKS: Used Thixotropic 8% Kal-Seal, 2% CC by Allied
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID NOT) OBSERVE THIS PLUGGING.

SIGNED [Signature]
(TECHNICIAN) **RECEIVED** P-2/3
KANSAS CORPORATION COMMISSION

INVOICED
DATE 6-12-98
NO. 50764

JUN 03 1998

CONSERVATION DIVISION
WICHITA, KS