

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-071-20751-00-00
Spot: N2NWNE Sec/Twnshp/Rge: 15-20S-42W
330 feet from N Section Line, 2100 feet from E Section Line
Lease/Unit Name: DEARLD SMITH Well Number: 1-15
County: GREELEY Total Vertical Depth: 5300 feet

Operator License No.: 9262
Op Name: LOWRY EXPLORATION, INC.
Address: PHILTOWER BLDG - #1702 427 S. BOST
TULSA, OK 74103

Conductor Pipe: Size feet: \$172.25
Surface Casing: Size 13.375 feet: 491
Production: Size feet:
Liner: Size feet:

Well Type: DH UIC Docket No: Date/Time to Plug: 03/03/2002 5:45 AM
Plug Co. License No.: 5382 Plug Co. Name: CHEYENNE DRILLING, INC.
Proposal Rcvd. from: LOU LUNSFORD Company: CHEYENNE DRILLING, INC. Phone: (620) 277-2062

Proposed Plugging Method: 1ST PLUG AT 1880' WITH 50 SX CMT. 2ND PLUG AT 1300' WITH 80 SX CMT. 3RD PLUG AT 750' WITH 40 SX CMT. 4TH PLUG AT 520' WITH 80 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 03/03/2002 8:30 AM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

1ST PLUG AT 1880' WITH 50 SX CMT. 2ND PLUG AT 1300' WITH 80 SX CMT. 3RD PLUG AT 750' WITH 40 SX CMT. 4TH PLUG AT 520' WITH 80 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

RECEIVED
MAR 06 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

Signed

(TECHNICIAN)

RECORDED

MAR 04 2002

Form CP-2/3

Mar 6-02

200.2061459

MP