

To:

1 080108

3-13

API NUMBER 15-071-20,429-00-00

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

App. S/2 SE NW NE SEC. 23, T 20 S, R 43 W/X

130 S. Market, Room 2078

Wichita, KS 67202

4125 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 5152

Lease Name BLM Well # 1

Operator: Lee Banks d/b/a Banks Oil Company

County Greeley 172.73

Name & Address 200 W. Douglas, Ste. 550

Well Total Depth 5315 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 358

Abandoned Oil Well Gas Well X Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Cheyenne Well Service License Number 6454

Address P.O. Box 384, Ness City, KS 67560-0384

Company to plug at: Hour: 1 p.m. Day: 13 Month: 3 Year: 19 97

Plugging proposal received from Gary Sharp

(company name) Sharp Engineering (phone) 316-262-3596

Perfs: 4 1/2" at 5314' w/150 sx cement, CIBP at 5150', Squeezed from 2000-200' w/200 sx cement,

Perfs at 5082-94, 5178-64'

1st plug pump 2 sx hulls and 25 sx cement, gel spacer to 2500',

2nd plug cement from 2500-0',

Top out backside with cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 5 p.m. Day: 13 Month: 3 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug pumped down 2 3/8" tubing set at 5100' with 21 sx gel and 25 sx cement and 200 lbs. hulls,

2nd plug pulled tubing to 1800' and pumped 65 sx cement,

3rd plug pulled to 900' and pumped 40 sx cement.

Pressured up 8 5/8" X 4 1/2" to 300# and held.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery. (if additional description is necessary, use BACX of this form.)

(did / HIXX) observe this plugging.

DATE MAR 21 1997

Signed Kevin P. Shute (TECHNICIAN)

INV. NO. 47782

RECEIVED KANSAS CORP COMM 1998 MAR 20 11:39