

1 070941

4-24

358

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
209 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 071-20,355-00-00

C NW, SEC. 33, T 20 S, R 39 W/X

3960 feet from S section line

3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7271

Lease Name Klein Well # 2

Operator: Bartling Oil Company

County Greeley 95.22

Name & Address 8550 Katy Freeway, Ste. 128

Well Total Depth 2930 feet

Houston, TX 77024

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 305

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Bartling Oil Company License Number 7271

Address 8550 Katy Freeway, Ste. 128, Houston, TX 77024

Company to plug at: Hour: 11:45 a.m. Day: 24 Month: 4 Year: 19 91

Plugging proposal received from Terry Maxwell

(company name) Bartling Oil Company (phone) 713-465-1093

were: 4 1/2" at 2923' w/550 sx cement, PBD 2810', Perfs at 2792-2803'

1st plug pump 2 sx hulls and 150 sx cement,

2nd plug check backside.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:30 p.m. Day: 24 Month: 4 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped 200 lbs. hulls and 120 sx cement down 4 1/2",

Maximum pressure 500 psi and shut in 100 psi.

Backside would not take.

RECEIVED STATE CORPORATION COMMISSION

APR 26 1991

CONSERVATION DIVISION

Remarks: Used 50/50 Pozmix 6% gel by Allied. No casing recovery, casing cemented to surface. (If additional description is necessary, use BACK of this form.)

INVOICED

(do not xxxxxx) observe this plugging.

Signed Dan Anderson (TECHNICIAN)

DATE 5-7-91

INV. NO. 31764