

1 100052.

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-071-20,361-00-00
C SW SW SE, SEC. 29, T 20 S, R 39 W EX

TECHNICIAN'S PLUGGING REPORT

330 feet from ~~WYS~~ section line
2310 feet from ~~WZE~~ section line

Operator License # 7271

Lease Name Weibert Well # 1

Operator: Bartling Oil Company

County Greeley 93.41

Name & Address 8550 Katy Freeway # 128

Well Total Depth 2874 feet

Houston, TX 77024

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 293

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Cheyenne Drilling, Inc. License Number 5382

Address Box 916, Garden City, KS 67846

Company to plug at: Hour: 1:00 am Day: 4 Month: April Year: 19 85

Plugging proposal received from Terry Maxwell

(company name) Cheyenne (phone) 316-277-2062

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2395' with 50 sx cement

2nd plug at 1430' with 50 sx cement

3rd plug at 800' with 40 sx cement

4th plug at 345' with 40 sx cement

solid bridge

5th plug hulls - plug at 40' Plugging Proposal Received by [Signature] (TECHNICIAN)
Cement to surface with 10 sx cement

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 3:00 am Day: 4 Month: April Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2395' with 50 sx cement, 2nd plug at 1430' with 50 sx cement, 3rd plug at 800' with 40 sx cement, 4th plug at 345' with 40 sx cement, 5th & 6th plug solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

APR 12 1985

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton
(if additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

I ~~will~~ (did not) observe this plugging.

Signed [Signature] (TECHNICIAN) SD

DATE 4-16-85

INV. NO. 7740
4-1

CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: 3 month 29 day 85 year

API Number is 071-20,361-00 *WALL*
plug down 3:00 AM 4-4-85
C. SW. SW. SE Sec 29. Twp. 20. S. Rge. 39 E. 1 West

OPERATOR: License # 7271

Name Bartling Oil Company
Address 8550 Katy Freeway #128
City/State/Zip Houston, Texas 77024
Contact Person Carl S. Graef
Phone 713.465-1093

Clyde Blugger

330 Ft North from Southeast Corner of Section
330 Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5382

Name Cheyenne Drilling
City/State Garden City, KS 67846

Nearest lease or unit boundary line 330 feet
County Greeley
Lease Name Weibert Well# 1

Well Drilled For: Well Class: Type Equipment:
 Oil Swd Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth
Projected Total Depth 3200 feet
Projected Formation at TD Ft. Riley
Expected Producing Formations Chase

Depth to Bottom of fresh water 250 feet
Lowest usable water formation Dakota
Depth to Bottom of usable water 1200 feet
Surface pipe by Alternate: 1 1/2"
Surface pipe to be set 275 feet
Conductor pipe if any required feet
Ground surface elevation 3519 feet MSL
This Authorization Expires 9-26-85
Approved By 3-26-85 *KC*

I certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

Date 3/26/85 Signature of Operator or Agent *Raguel A. Raben* Title As agent

set 279' of 8 5/8 on 3/31/85 *MHC/LOHE 3-26-85*

RECEIVED
STATE CORPORATION COMMISSION

APR 12 1985

CONSERVATION DIVISION
Wichita, Kansas