

1 053830

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 071-20,354 -00-00

C NW, SEC. 21, T 20 S, R 39 W/E

3960 feet from S section line

3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7271

Lease Name Miller Well # 4

Operator: Bartling Oil Company

County Greeley 95.55

Name & Address 8550 Katy Freeway, # 128

Well Total Depth 2940 feet

Houston, TX 77024

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 305

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Higginbottom Engineering, Inc. License Number

Address Box 6, Liberal, KS 67901

Company to plug at: Hour: 2:00 pm Day: 22 Month: May Year: 19 85

Plugging proposal received from Terry Maxwell

(company name) Higginbottom (phone) 316-624-3767

4 1/2" circulated on the backside

were: 4 1/2" at 2932' PBTD 2932' Perfs at 2849-2858, 2864-70, 2805-2814

Squeeze well with 2 sx hulls, 40 sx cement, 8 sx gel, and 100 sx cement.

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None Clyde Wiley observed the plugging

Operations Completed: Hour: 2:40 pm Day: 22 Month: May Year: 19 85

ACTUAL PLUGGING REPORT Squeezed well with 2 sx hulls, 40 sx cement, 8 sx gel and 100 sx cement.

RECEIVED STATE CORPORATION COMMISSION

MAY 28 1985

Shut in pressure 100 psi

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel 3% cc by Halliburton (If additional description is necessary, use BACK of this form.)

Clyde Wiley observed the plugging (If additional description is necessary, use BACK of this form.)

Signed Richard W. Lacey (TECHNICIAN)

INVOICED DATE 5-29-85 INV. NO. 8285

JUN 25 1985