

1 000282

R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 025-20,878 0000

SE SE NW, SEC. 33, T 33 S, R 23 W/E

2970 feet from N/S section line

2970 feet from N/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5313

Lease Name McMillion "B" Well # 1

Operator: F & M Oil Co., Inc.

County Clark 186-72

Name & Address 422 Union Center

Well Total Depth 5745 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 438 1/2

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Union Drilling Co., Inc. License Number 5103

Address 422 Union Center Building, Wichita, KS 67202

Company to plug at: Hour: 7:00 pm Day: 24 Month: January Year: 19 85

Plugging proposal received from T. F. Brown

(company name) Union Drilling (phone) 316-262-1872

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 960' with 50 sx cement

RECEIVED  
STATE CORPORATION COMMISSION

2nd plug at 480' with 40 sx cement

FEB 04 1985

solid bridge -

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

CONSERVATION DIVISION  
Wichita, Kansas

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by R. B. Brantluttan  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 9:00 pm Day: 24 Month: January Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 960' with 50 sx cement, 2nd plug at 480' with 40

sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface

with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to

circulate mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun  
(if additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

Signed R. B. Brantluttan SWD  
(TECHNICIAN)

DATE 2-8-85

INV. NO. 6884  
1-24