

1080308

TO: STATE CORPORATION COMMISSION

API NUMBER 15-071-20,051-00-00
C NW SEC. 17, T 20 S, R 39 W

CONSERVATION DIVISION - PLUGGING SECTION 1320 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1320 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME WATSON B WELL # 1
COUNTY GREELEY 95.88

TECHNICIAN'S PLUGGING REPORT 8/25

OPERATOR LICENSE # 32340 WELL TOTAL DEPTH 2950 FEET

OPERATOR: BLUEGRASS ENERGY INC. PRODUCTION CSG: SIZE 5 1/2" @ 2946' WITH 485 SX

NAME AND 5727 S LEWIS, SUITE 700 SURFACE CASING: SIZE 8 5/8" @ 286' WITH 200 SX

ADDRESS TULSA, OK 74105

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR SWIFT SERVICES, INC LICENSE NUMBER 32382

ADDRESS PO BOX 466, NESS CITY, KS 67560

COMPANY TO PLUG AT: HOUR: 9:30 AM DAY: 25 MONTH: 08 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM DAVE OLSON

(COMPANY NAME) SWIFT SERVICE, INC (PHONE) 785-798-2300

WERE: PERFS AT 2854-66 & 2797-2814

PUMP DOWN 5 1/2" 235 SX CEMENT WITH 400# HULLS MIXED IN FIRST 50 SX CEMENT. MAXIMUM PSI 500#.

SHUT IN AT 200#. PUMP DOWN 8 5/8" X 5 1/2" ANNULUS 50 SX CEMENT. MAXIMUM PSI 200#. SHUT IN AT

100#.

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 11:45 AM DAY: 25 MONTH: 08 YEAR: 2000

ACTUAL PLUGGING REPORT _____

PUMPED DOWN 5 1/2" 235 SX CEMENT WITH 400# HULLS MIXED IN FIRST 50 SX CEMENT. MAXIMUM PSI 500#.

SHUT IN AT 200#. PUMPED DOWN 8 5/8" X 5 1/2" ANNULUS 50 SX CEMENT. MAXIMUM PRESSURE 200#.

SHUT IN AT 100#.

RECEIVED
STATE CORPORATION COMMISSION

SEP 06 2000

REMARKS: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

CONSERVATION DIVISION
Wichita, Kansas

I (DID) OBSERVE THIS PLUGGING.

SIGNED Kevin D. Strube
(TECHNICIAN) FORM CP-2/3

DATE 9/7/00
INV. NO. 2001060610

[Handwritten signature]