

1 0531

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 071-20,340-00-00

C SW SW SW SEC. 10, T 20 S, R 39 W/E

330 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7271

Lease Name Miller Well # 3

Operator: Bartling Oil Company

County Greeley 95.88

Name: 8550 Katy Freeway, Suite 128

Well Total Depth 2950 feet

Address: Houston, TX 77024

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 290

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Higginbottom Engineering, Inc. License Number

Address Box 6, Liberal, KS 67901

Company to plug at: Hour: 11:00 am Day: 22 Month: May Year: 19 85

Plugging proposal received from Terry Maxwell

(company name) Higginbottom (phone) 316-624-3767

4 1/2" circulated on the backside
were: 4 1/2" casing at 2919' PRTD 2919' Perfs at 2850-58, 2872-78, 2813-2825

Squeeze well with 2 sx hulls, 40 sx cement, 8 sx gel and 100 sx cement.

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None
Clyde Wiley observed the plugging

Operations Completed: Hour: 12:10 pm Day: 22 Month: May Year: 19 85

ACTUAL PLUGGING REPORT squeezed well with 2 sx hulls, 40 sx cement, 8 sx gel and 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

MAY 28 1985

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel 3% cc by Halliburton
(If additional description is necessary, use BACK of this form.)

Clyde Wiley observed the plugging
(If additional description is necessary, use BACK of this form.)

Signed Richard W. Lacey
(TECHNICIAN)

INVOICED
DATE 5-29-85
INV. NO. 8284 5-22

JUN 25 1985