

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-071-20135-00-00
Spot: CSWNE Sec/Twnshp/Rge: 6-20S-39W
3300 feet from S Section Line, 1970 feet from E Section Line
Lease/Unit Name: KUTTNER Well Number: 1
County: GREELEY Total Vertical Depth: 2878 feet

Operator License No.: 32340
Op Name: BLUEGRASS ENERGY, INC.
Address: 5727 S. LEWIS, STE 720
TULSA, OK 74105

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 260 WITH 200 SX CMT
Production: Size 4.5 feet: 2878 WITH 150 SX CMT
Liner: Size feet:

\$93.54

Well Type: GAS UIC Docket No: Date/Time to Plug: 09/12/2001 8:50 AM

Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: DAVE OLSON Company: BLUEGRASS ENERGY Phone: (316) 376-8190

Proposed Plugging Method: PERFORATE AT 1200'. PUMP 80 SX CMT OVER CASING CAPACITY OR CIRCULATE TO SURFACE. PUMP 200 SX CMT DOWN BACKSIDE.

Plugging Proposal Received By: KEVIN STRUBE

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 09/12/2001 1:30 PM

KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 2878'. PERFS AT 2832-2842'. TUBING STUCK IN HOLE. SHOT TUBING OFF AT 1250'. CASING LEAK AT APPROXIMATELY 1500'. PUMPED 100 SX CMT WITH 100# HULLS. DISPLACED TO 1100'. MAXIMUM PRESSURE 1200#. SHUT IN AT 1200# FOR 2 HOURS. PERFORATED AT 1200'. PUMPED DOWN 4 1/2" PRESSURED UP TO 1300#. COULDN'T PUMP INTO. PERFORATED AT 800'. PUMPED DOWN 4 1/2" CIRCULATED CMT TO SURFACE WITH 200 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed

Kevin D. Strube

(TECHNICIAN)

RECEIVED

SEP 25 2001
09-25-01
KCC WICHITA

9-25-01
2002060605

SEP 17 2001

Form CP-113