


15-203-20047-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Wichita County. Sec. 10 Twp. 17 Rge. 35 ~~N~~/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
470' FNL 470' FEL of NW $\frac{1}{4}$
Lease Owner Stelbar Oil Corporation, Inc.
Lease Name Barnhart Well No. 1
Office Address 450 Fourth Financial Center, Wichita, Ks
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

Dry Hole
Date Well completed Dec. 7 1979
Application for plugging filed Dec. 21 1979
Application for plugging approved Dec. 18 1979
Plugging commenced Dec. 7 1979
Plugging completed Dec. 7 1979
Reason for abandonment of well or producing formation _____

Dry Hole
If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	350	8-5/8"	350	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set plug at 980 w/ 70 sx 50/50 Poz 6% Gel, set at 340 w/ 20 sx 40-0 w/ 10 sx 5 sx RH

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Robert W. Patton (employee of owner) or ~~owner or operator~~
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert W. Patton
450 Fourth Financial Center, Wichita, Ks
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of December, 1979

My commission expires May 7, 1982.

Talia Zuhars
Notary Public.

RECEIVED
CONSERVATION DIVISION
Wichita, Kansas
DEC 26 1979

15-203-20047-00-00

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

Barnhart #1
C-NE-NW Sec 10-17S-35W
Wichita County Kansas

Commenced: 11-24-79

Completed: 12-7-79

OPERATOR: Stelbar Oil Co.

Depth		Formation	Remarks
From	to		
0	360	Sand-Blue Shale	Ran 8 jts of 28# 8 5/8" csg set @ 350' Cemented w/ 225 sks Class H w/ 3% CC
360	1295	Shale	
1295	2063	Shale-Sand	PD @ 11:40 p.m. 11-25-79
2063	2214	Shale	
2214	3270	Shale-Lime	
3270	3678	Line	
3678	3797	Line-Shale	
3797	3928	Shale-Lime	
3928	4041	Line	
4041	4171	Shale-Lime	
4171	4364	Line	
4364	4469	Shale-Lime	
4469	4916	Line-Shale	
4916	5075	Lime	
	5075 TD		DRY & ABANDONED

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above
Drillers' Well Log is true and correct to the best of my knowledge and belief and
according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton II
JAMES S. SUTTON II

Subscribed and sworn to before me this 11th day of December, 1979.

Elizabeth J. Edwards
ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1983.

