


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW&SW&SE" or footage from lines Wichita County. Sec. 21 Twp. 17S Rge. (E) 38(W)
Lease Owner Arvel C. Smith & Toto Gas Company
Lease Name Bauck Well No. 1
Office Address 814 North Mission, Wichita 6, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 5, 19 62
Application for plugging filed " 19 "
Application for plugging approved " 19 "
Plugging commenced " 19 "
Plugging completed " 19 "
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 5151 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|--------------|------|------|--------|--------|------------|
| | Surface Pipe | 0 | 303' | 8 5/8" | | No |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

0' to 30' Ten sack cement plug
30' to 230' Heavy mud
230' to 290' Twenty sack cement plug
290' to 700' Heavy mud
700' to 790' Thirty sack cement plug
790' to Total Depth Heavy mud

RECEIVED
STATE CORPORATION COMMISSION

OCT 10 1962
10-12-62
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Natural Gas Drilling, Inc.
Address Box 1615, Oklahoma City, Oklahoma

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Arvel C. Smith (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Arvel C. Smith
814 North Mission, Wichita 6, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of October, 19 62

My commission expires September 30, 1966

Notary Public.

DRILLERS LOG

Reverse Orion Skin
NO. 1 BAUCK
SW SW Sec. 21-178-38W
Wichita County, Kansas

Commenced September 19, 1962

Completed October 5, 1962 - Dry and Abandoned.

8 5/8" surface casing set at 303 feet, cemented with 250 sacks of cement; circulated to surface.

Formation Record:

| | |
|--------------|--------------------------------|
| 0 - 580' | Shale and Sand |
| 580 - 670' | Sand |
| 670 - 1860' | Shale and Sand |
| 1860 - 2580' | Shale and Anhydrite |
| 2580 - 4000' | Shale, Lime and Chalk |
| 4000 - 4880' | Lime, Chalk with Shale streaks |
| 4880 - 5056' | Shale with Sand streaks |
| 5056 - 5150' | Lime |
| 5150' | Total Depth |

RECEIVED
STATE CORPORATION COMMISSION
OCT 19 1962
CONSERVATION DIVISION
Wichita, Kansas

Hole filled with heavy mud; 30 sack cement plug set 790' to 700' thru drill pipe; Heavy mud 700' to 290'; 20 sack cement plug set at 290' to 230'; Heavy mud 230' to 30'; 10 sack cement plug 30' to surface.

I hereby certify that the above and foregoing is a true and accurate report of the drilling and abandonment of the well described.

Dated October 9, 1962.

G. Howard

Subscribed and sworn to before me, a Notary Public, this 9th day of October, 1962.

Ernie B. Reid
Notary Public

Plugging Inspector: Eldon Petty
Hays, Kansas

Reverse Orion Skin