


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Wichita County. Sec. 25 Twp. 18S Rge. 9 (E) 36 (W)
Location as "NE/CNW%SW%" or footage from lines C SE SE
Lease Owner Musgrove Petroleum Corporation
Lease Name RICHARDSON Well No. 1
Office Address 801 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed September 9 1957
Application for plugging filed verbally - September 8 1957
Application for plugging approved verbally - September 8 1957
Plugging commenced September 9 1957
Plugging completed September 9 1957
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes - verbally

Name of Conservation Agent who supervised plugging of this well R. M. Brundege
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5200 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	472'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 465'
Set first plug at 465' w/20 sx cement
Filled hole with heavy mud to 35'
Set 2nd plug at 35' w/10 sx cement

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Musgrove Petroleum Corporation
Address 801 Union Center, Wichita, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
I, Emil E. Bowers (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Emil E. Bowers
801 Union Center, Wichita, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of September, 19 57

My commission expires June 16, 1959

Leah Joyce Heyke
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
SEP 13 1957
WICHITA, KANSAS

PLUGGING
FILE SEC 25 T 18 R 36W
BOOK PAGE 44 LINE 30

15-203-00013-00-00

CONTRACTOR'S WELL LOG

COMPANY: Musgrove Petroleum Corporation
 CONTRACTOR: Musgrove Petroleum Corporation
 FARM: RICHARDSON #1
 LOCATION: C SE SE, Sec. 25-18S-36W
 Wichita County, Kansas
 COMMENCED: August 24, 1957
 COMPLETED: September 9, 1957

0	480	Sand & clay
480	1185	Sand, shale & shells
1185	1500	Shale & shells
1500	1645	Shale
1645	2045	Anhydrite & shale
2045	2110	Shale & shells
2110	2380	Shale & lime shells
2380	2534	Anhydrite & shale
2534	2820	Shale & anhydrite streaks
2820	2885	Anhydrite & shale
2885	3040	Shale & shells
3040	3230	Shale & lime
3230	3821	Lime
3821	3955	Lime & shale
3955	4875	Lime
4875	4990	Lime, shale, sand
4990	5039	Sand
5039	5200	Lime
	5200	Rotary Total Depth

Set 8-5/8" surface at 472' with 250 sx cement, 2% calcium chloride.

Dry and Abandoned

ELEVATION:	3222' D. F.	Heebner	4019' (- 794)
	3214' Gr.	Lansing	4066' (- 841)
	3225' K. B.	Marmaton	4531' (-1306)
SCHLUMBERGER TOPS:		Cherokee	4707' (-1482)
Wabaunsee	3612' (- 387)	Morrow Shale	4866' (-1641)
Topeka	3836' (- 611)	Mississippi	5050' (-1821)

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, EMIL E. BOWERS, do hereby certify that the above and foregoing is a true and correct copy of the log of the RICHARDSON #1, C SE SE, Section 25-18-36W, Wichita County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

BY Emil E. Bowers
Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 12th day of September, 1957.

Leah Jave Neffe
Notary Public

My commission expires June 16, 1959.

PLUGGING
 FILE SEC 25 T 18 R 36W
 BOOK PAGE 44 LINE 30