

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-203-20031-00-00  
Spot: NWSESWSW Sec/Twnshp/Rge: 34-20S-38W  
660 feet from S Section Line, 660 feet from W Section Line  
Lease/Unit Name: CALDWELL C Well Number: 1  
County: WICHITA Total Vertical Depth: 4880 feet

Operator License No.: 6568  
Op Name: KAISER-FRANCIS OIL COMPANY  
Address: PO BOX 21468  
TULSA, OK 74121

Conductor Pipe: Size feet: \$158.60  
Surface Casing: Size 8.625 feet: 339  
Production: Size 5.5 feet: 4878 WITH 150 SX CMT  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/21/2002 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: Company: Phone:

Proposed Plugging Method: CIBP @ 4680' & 2 SX CMT. LOAD HOLE & PRESSURE UP. PERFORATE AT 1200'. PUMP 80 SX CMT - 200# HULLS - 100 SX CMT. PUMP 200 SX CMT DOWN BACKSIDE.

Plugging Proposal Received By: STEVE DURRANT Witness Type: Plugging Operations Were Not Witnessed  
Date/Time Plugging Completed: 01/21/2002 11:30 AM KCC Agent: STEVE DURRANT

Actual Plugging Report:

PBTD 4852'. PERFS AT 4788-94, 4820-30, 4836-42'. SET CIBP @ 4680.5' WITH 2 SX CMT. LOADED HOLE & PRESSURED TO 300#. PERFORATED AT 1200'. PUMP 80 SX CMT - 200# HULLS - 100 SX CMT. SHUT IN PRESSURE 850#. TIED ONTO BACKSIDE. PUMPED 200 SX CMT. SHUT IN AT 300#.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERY.

Plugged through: CSG

District: 01

Signed

Steve Durrant

(TECHNICIAN)

RECEIVED

JAN 25 2002  
01-25-02  
KCC WICHITA

Jan 25, 02  
2002061317

JAN 22 2002

Form CP-2/3