

To: 1 000105 3-4  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION App.  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 203-20,037-00-00  
C. SE SW, SEC. 34, T 20 S, R 38 W/4  
740 feet from S section line  
1831 feet from W/4 section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6568

Lease Name Caldwell C Well # 2

Operator: Kaiser-Francis Oil Company

County Wichita 160.87

Name & Address P.O. Box 21468

Well Total Depth 4950 feet

Tulsa, OK 74121-1468

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 342

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529

Address P.O. Box 209, Chase, KS 67524-8170

Company to plug at: Hour: 9:30 a.m. Day: 4 Month: 3 Year: 19 97

Plugging proposal received from John Glenn

(company name) Kaiser-Francis Oil Co. (phone) 316-564-3214

logs: 4 1/2" at 4950', CIBP @ 4820 & 4723', Perfs at 4772-86, 4868-76', Casing leaks 1845' to top of cement; approx. 4000'

1st plug at 1800' with 50 sx cement, 2nd plug at 1200' with 80 sx cement,  
3rd plug at 600' with 50 sx cement, 4th plug at 370' with 50 sx cement.  
5th plug top off with 10 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:45 P.M. Day: 4 Month: 3 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug shot casing at 1805' and pumped 500 lbs. hulls and 50 sx cement, displaced to 1700',

2nd plug pulled casing to 1200' and pumped 18 sx gel and 80 sx cement, then 2 sx gel. Pressured up to 500#. Tried to release, came back, displaced cement back down, shut in 1 hr.

Released 5 bbl. back. 3rd plug pulled casing to 600' and pumped 30 sx cement, had circulation, 4th plug pulled to 370' and pumped 50 sx cement, 5th plug topped off with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1805' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
I (date) observe this plugging.

DATE 3-12-97

Signed Kevin D. Shuler (TECHNICIAN)

NO. 47727  
3-4