

To: 1
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

12-5
API NUMBER 15-203-20,123-00-00
80' N & 20' E of
SE SW, SEC. 34, T 20 S, R 38 W/4
740 feet from S section line
2000 feet from WE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6568
Operator: Kaiser-Francis Oil Company
Name & Address: P.O. Box 21468
Tulsa, OK 74121-1468

Lease Name Caldwell C Well # 3
County Wichita 162.50
Well Total Depth 5000 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 273

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A
Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Co., Inc. License Number 30606
Address 250 N. Water, Ste. 300, Wichita, KS 67202

Company to plug at: Hour: 10:30 p.m. Day: 4 Month: 12 Year: 19 96
Plugging proposal received from Ed McKenna
(company name) Murfin Drilling Co., Inc. (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2275'
1st plug at 2275' with 50 sx cement, 2nd plug at 1120' with 80 sx cement,
3rd plug at 675' with 40 sx cement, 4th plug at 300' with 50 sx cement,
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement.


Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None
Operations Completed: Hour: 4 a.m. Day: 5 Month: 12 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug at 2275' with 50 sx cement,
2nd plug at 1120' with 80 sx cement, 3rd plug at 675' with 40 sx cement,
4th plug at 300' with 50 sx cement, 5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement, 12-09-96
7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# flowseal by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
observe this plugging.

Signed 
(TECHNICIAN)

DATE DEC 14 1996

WV. NO. 47164

12-5

FOR KCC USE:

EFFECTIVE DATE: 9-29-96

DISTRICT #

SGAT Yes No

State of Kansas

NOTICE OF INTENTION TO DRILL 203-20, 123-00-00

FORM C-1 7/91

FORM MUST BE TYPED

FORM MUST BE SIGNED

ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date October 15 1996
month day year

Spot 80N & 70'E OF East
SE SW Sec 34 Twp 20 S Rg 38 X West

OPERATOR: License # 6568
Name: Kaiser-Francis Oil Company
Address: P.O. Box 21468
City/State/Zip: Tulsa, OK 74121-1468
Contact Person: Drew Tyler
Phone: 918-491-4343

740 feet from South/ North line of Section
2000 feet from East West line of Section
IS SECTION X REGULAR IRREGULAR?
(NOTE: Locate well on the Section Plat on Reverse Side)

County: Wichita
Lease Name: Caldwell "C" Well #: 3
Field Name: Panama RUPT

* CONTRACTOR: License #: unknown
Name: ADVISE ON ACO-1 Murtin

* Is this a Prorated/Spaced Field? yes X no

Well Drilled For: Well Class: Type Equipment:
X Oil Enh Rec X Infield X Mud Rotary
Gas Storage Pool Ext Air Rotary
OWWO Disposal Wildcat Cable
Seismic # of Holes Other

Target Formation(s): MORROW
Nearest lease or unit boundary: 740'
Ground Surface Elevation: est. 3405 feet MSL
Water well within one-quarter mts: yes X no
Public water supply well within one mile: yes X no
Depth to bottom of fresh water: 220'
Depth to bottom of usable water: 1110'
Surface Pipe by Alternate: 1 X 2
Length of Surface Pipe Planned to be set: 350'
Length of Conductor pipe required:
Projected Total Depth: 5000'
Formation at Total Depth: MORROW
Water Source for Drilling Operations:
well farm pond X other

If OWWO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

DWR Permit #:
Will Cores Be Taken?: yes X no
If yes, proposed zone: 240' Alt. FH Reg.

Directional, Deviated or Horizontal wellbore? yes X no
If yes, true vertical depth:
Bottom Hole Location:

* PRORATED AND SPACED IN CHASE AND COUNCIL GROVE.

Exp. 3/24/97

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-

Pusher Ed McKenna
SPUD DATE 1/26-96 INIT BSM
LENGTH SURFACE PLANNED 350
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 2 1/2" @ 273 CONDUCTOR
ANHYDRITE T- B-220 ELEVATION
TD 500 FORMATION Morrow
RAR PIPE @ DV TOOL ALT II DONE
SX SX Y N SX
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ SX
Anhydrite Base @ 2275 Ft. W/ 50 SX
1/2 Base Anhy. @ 1120 Ft. W/ 80 SX
1/2, 1/2 Plug @ 675 Ft. W/ 40 SX
Bottom Surface @ 300 Ft. W/ 50 SX
40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX
WATER WELL SX (Irr. Well Pond)
TECHNICIAN SW DATE 12-4-96
TYPE OF CEMENT 60/40 6 7/8 1/4 Flossid
STARTING TIME 10:30 (AM/PM) DATE 12-4-96
COMPLETION TIME 4:00 (AM/PM) DATE 12-5-96
CEMENT COMPANY Allied