

1100078

15-203-30055-00-01

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Comp. 8-24-67

C SE SE, SEC. 33, T 20 S, R 38 W/~~E~~

660 feet from N/S section line

660 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5921

Lease Name Caldwell Well # 1

Operator: Jon Carroll Oil (Was Davidor & Name & Davidor)

County Wichita 166.95

Address P. O. Box 1987

Well Total Depth 5137 feet

Great Bend, KS 67530

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 306

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address P. O. Box 698, Great Bend, KS 67530

Company to plug at: Hour: 10:00 am Day: 13 Month: February Year: 1986

Plugging proposal received from Deacon Pulley

(company name) Rockhold (phone) 316-792-2506

were: 4 1/2" at 5133' Perfs at 4969-76'

1st plug sand back to 4900' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 50 sx cement, 3 sx hulls, 15 sx gel, release 8 5/8" rubber plug and pump 200 sx cement.

Steve Durrant gave orders

Plugging Proposal Received by [Signature] (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:30 am Day: 13 Month: February Year: 1986

ACTUAL PLUGGING REPORT 1st plug sanded back to 4900' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 50 sx cement, 3 sx hulls, 15 sx gel, released 8 5/8" rubber plug and pumped 200 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

FEB 17 1986

Maximum pressure 700 psi and shut in 100 psi

Remarks: Recovered 1000' 4 1/2" casing. Used 60/40 Pozmix 6% gel with Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED

(did / ~~not~~) observe this plugging.

DATE 2-17-86

Signed [Signature] (TECHNICIAN)

INV. NO. 12621