

1-1080181

3-3

5.

TO:

STATE CORPORATION DIVISION

CONSERVATION DIVISION - PLUGGING SECTION

WICHITA STATE OFFICE BUILDING

130 S. MARKET, WICHITA, KS 67202

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE NUMBER: 100

OPERATOR: KCC

NAME AND 304 WEST MCARTOR

ADDRESS: DODGE CITY, KS 67801

ABANDONED - OIL WELL

GAS WELL X

INPUT WELL

SWD WELL

D/A

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: ALLIED CEMENTING LICENSE NUMBER:

ADDRESS: BOX 628, GREAT BEND, KS 67530:

COMPANY TO PLUG AT - HOUR: 12:45PM

DATE: 3-3-98

PLUGGING PROPOSAL RECEIVED FROM: Kevin Strube

COMPANY NAME: KCC

PHONE NUMBER: 316-225-8888

WERE: pump 400 lbs of hulls, fill 5 1/2" casing with cement, pressure test 8 5/8" x 5 1/2" annulas with cement

PLUGGING REPORT RECEIVED BY: Kevin Strube, Technician

PLUGGING OPERATION ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED - HOUR: 2:30PM

DATE: 3-3-98

ACTUAL PLUGGING REPORT: 1st plug pumped 200 lbs hulls with 200 lbs hulls mixed in cement, total of 225 sx, max pressure 600 psi and shut in at 500 psi. Tied on to 8 5/8" x 5 1/2" annulas and pumped 25 sx cement - 500 psi.

REMARKS: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.

I (DID / XXXXXXXX) OBSERVE THIS PLUGGING.

Kevin D Strube

Technician

RCW
03-11-98
API NUMBER 15-203-20,055-00-00
C NE SEC. 9, T. 20 S, R. 38 (W)
3960 FEET FROM SOUTH SECTION LINE
1320 FEET FROM EAST SECTION LINE

LEASE NAME: COLLINGWOOD ESTATE WELL # 3

COUNTY: WICHITA

WELL TOTAL DEPTH: 3250 FEET

PRODUCTION CSG - SIZE: 5 1/2 FEET 3240

SURFACE CASING - SIZE: 8 5/8 FEET 402

CONDUCTOR PIPE - SIZE: FEET