

To: 1 060152
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

12-15

API NUMBER 15-203-20,097-00-00

1210

C W/2 NW, SEC. 15, T 20 S, R 38 W/EX

1320 feet from NS section line

660 feet from WE section line

Lease Name Kropp Well # 1-15

County Wichita

Well Total Depth 5030 163.48 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 470

TECHNICIAN'S PLUGGING REPORT

Operator License # 6113

Operator: Landmark Oil Exploration, Inc.

Name & Address

250 N. Water, Ste. 308

Wichita, KS 67202

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Company, Inc. License Number 30606

Address 250 N. Water, Ste. 300, Wichita, KS 67202

Company to plug at: Hour: 4 a.m. Day: 15 Month: 12 Year: 19 92

Plugging proposal received from Rodney Farr

(company name) Murfin Drilling Company, Inc. (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2310-25'

1st plug at Hugoton/Council Grove with 100 sx cement,

2nd plug at 2350' with 50 sx cement, 3rd plug at 1500' with 50 sx cement,

4th plug at 900' with 50 sx cement, 5th plug at 500' with 50 sx cement,

6th plug at 40' with 10 sx cement, 7th plug to circulate rathole with 15 sx cement,

8th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by _____ Case Morris
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 6:45 a.m. Day: 15 Month: 12 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 2350' with 50 sx cement,

2nd plug at 1500' with 50 sx cement, 3rd plug at 900' with 50 sx cement,

4th plug at 500' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.

(if additional description is necessary, use BACK of this form.)

~~XXXXX~~ did not observe this plugging.

INVOICED

DATE 1-19-93

INV. NO. 37219

Signed Case Morris
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION

DEC 22 1992

EFFECTIVE DATE: 12-6-92
DISTRICT: 1
SEAT: Yes X No

State of Kansas
NOTICE OF INTENTION TO DRILL 9-203-20,097-0000
ALL BLANKS MUST BE FILL

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date: December 1 1992
month day year

W/2 NW Sec 15 Twp 20-S Rg 38-W

OPERATOR: License # 06113
Name: Landmark Oil Exploration, Inc.
Address: 250 N. Water, Suite 308
City/State/Zip: Wichita, Kansas 67202
Contact Person: Jeff Wood
Phone: (316) 265-8181

1320 feet from SE CORNER / North line of Sect
660 feet from XX / West line of Sect
IS SECTION XX REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse S)
County: Wichita
Lease Name: Kropp Well #1-15
Field Name: Unnamed

CONTRACTOR: License #: 30606
Name: Murfin Drilling Company, Inc.

Is this a Prorated/Spaced Field? yes XX no
Target Formation(s): Morrow Sand
Nearest lease or unit boundary: 660'

Ground Surface Elevation: 3405 feet
Water well within one-quarter mile: yes XX
Public water supply well within one mile: yes XX

Well Drilled For: Well Class: Type Equipment:
XX Oil ... Enh Rec ... Infield XX Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OUVO ... Disposal ... XX Wildcat ... Cable
... Seismic; ... # of Holes ... Other

Depth to bottom of fresh water: 180'
Depth to bottom of usable water: ...
Surface Pipe by Alternate: 1 XX 2

If OUVO: old well information as follows:
Operator: ...
Well Name: ...
Comp. Date: ... Old Total Depth

Length of Surface Pipe Planned to be set: 200'
Length of Conductor pipe required: N/A
Projected Total Depth: 5100'

Formation at Total Depth: Mississippi
Water Source for Drilling Operations: well farm pond XX at

Directional, Deviated or Horizontal wellbore? yes XX no
If yes, true vertical depth: ...
Bottom Hole Location: ...

OUR Permit #: ...
Will Cores be Taken?: yes XX no
If yes, proposed zone: ...

Exp. 5/30/93

AFFIDAVIT

200' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A.

Pusher: Rodney Faust 097
SPUD DATE: 12-4-92 INIT. SN
LENGTH SURFACE PLANNED: 450'
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 1 1/2 @ 470 CONDUCTOR
ANHYDRITE T- 2310 B- 2325 ELEVATION
TD 5030 FORMATION
RAN PIPE @ DV TOOL ALT II DONE
SX SX Y N
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ 100 SX
Anhydrite Base @ 2150 Ft. W/ 50 SX
1/2 Base Anyh. @ 1500 Ft. W/ 50 SX
1/2, 1/2 Plug @ 900 Ft. W/ 50 SX
Bottom Surface @ 500 Ft. W/ 50 SX
40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX
WATER WELL SX (Irr. Well Pond Hauling)
TECHNICIAN CA DATE 12-11-92
TYPE OF CEMENT 60/40 670 1/4# ES.
STARTING TIME RECEIVED 12-15-92
COMPLETION TIME 4:45 (AM/PM) DATE 12-15-92
CEMENT COMPANY ALLIANCE